

ADDITIONS

1. Rooms 7 and 8.

- A. Add $\frac{1}{2}$ ton electric hoist and rail down center of rooms 7 and 8.
- B. Add circuit from panel PG-20 to rear of room 8 for $\frac{1}{2}$ ton electric hoist. Add switch and outlet for hoist.
- C. Add one circuit from panel PE-6 to front wall of room 8. (400 cycle)
- D. Add one circuit from panel PF-7 to front wall of room 8. (25 V DC)
- E. Add one circuit from panel PG-7 to left wall of room 7. (115 V)
- F. Add thermostat to rear wall of room 8.
- G. Make entrance into combined rooms 7 and 8 a double door.

2. Room 12.

- A. Widen door to 5 feet.
- B. Add circuit from panel PF-8 to service 6 DC outlets on front and right side of room.

3. Room 20.

- A. Add one 208 volt, 5 Kw outlet to left wall. Circuit from panel PD-6. Outlet to be three wire, one for ground.

4. Room 23.

- A. Add 3 ton Air-conditioner in corner of room, outside wall.
- B. Add 208 volt, 3 Kw outlet for air-conditioner. Outlet to be three wire, one for ground.
- C. Add sliding panels per attached sketches.

5. Room 43.

- A. Add two lighting fixtures, type "C-2".
- B. Add two 110 volt outlets to inside wall. Circuit may come from existing 50 cycle switch panel.

Room 5

ADD $\frac{1}{2}$ TON ELEC HOIST

Additions, continued.

6. Room 46.

- A. Add three lighting fixtures, type "C-3".
- B. Add three 110 volt outlets to inside wall. Circuit may come from existing 50 cycle switch panel.

7. Room 48.

- A. Add two lighting fixtures, type "C-3".
- B. Add three 110 volt outlets to inside wall. Circuit from panel PG-12-14-16.

8. Room 32.

- A. Add compressed air outlet on left wall.

9. Room 33.

- A. Add one 110 volt outlet on rear wall. Circuit from panel PG-8.

DELETIONS.

1. Room 4.
 - A. Delete electric chain hoist and rail from room.
 - B. Delete circuit from PG-20, switch and outlet.
2. Rooms 7 and 8.
 - A. Delete wall between rooms 7 and 8.
 - B. Delete thermostat from left wall of room 8.
3. Room 12.
 - A. Delete 60 A, 2 P, 125 V switch, 200 A, 3 P, 125 V switch and 100 A, 4 P, 250 V switch.
 - B. Delete two lighting fixtures in center of room.
4. Room 31.
 - A. Delete one lighting fixture.
5. Room 32.
 - A. Delete two lighting fixtures.
6. Room 33.
 - A. Delete two lighting fixtures.
7. Room 34.
 - A. Delete one out let from panel PG-8.